

(Formerly WEST BENGAL UNIVERSITY OF TECHNOLOGY)

<u>Main Campus: NH 12, Haringhata, Post Office - Simhat, Police Station – Haringhata, Pin - 741249</u> City Campus: BF-142, Sector -I, Salt Lake, Kolkata -700 064

Ref. No.: MAKAUT-WB/2021-22/STORE-COE&FINANCE/001/CORRIGENDUM

Dated: 29-11-2021

This is for information of all the bidders that following amendments /Corrigendum are being made in tender documents (Ref. No.: MAKAUT-WB/2021-22/STORE-COE&FINANCE/001/CORRIGENDUM dated 22-11-2021). Item Name: BOQ. The Specification of the said item should be read as follows:

The last date for submission for the tender is extended till 05-12-2021.

PROPOSED REVISED ESTIMATE FOR THE IGLOO SHAPED STORE OF MOULANA ABUL KALAM AZAD UNIVERSITY OF TECHNOLOGY WB AT HARINGHATA CAMPUS

BOQ							
Sl.No.	Item	Quantity	Unit		Rate		Amount
1	Ref PWD SCHEDULE 2017 Page No-1, Item No-2						
	Earth work in excavation of foundation trenches						
	or drains, in all sorts of soil (including mixed soil						
	but excluding laterite or sandstone) including						
	removing, spreading or stacking the spoils within						
	a lead of 75 m. as directed. The item includes						
	necessary trimming the sides of trenches,						
	levelling, dressing and ramming the bottom,						
	bailing out water as required complete. (a) Depth						
	of excavation not exceeding 1,500 mm.	2.340	Cum	₹	119.27	₹	279.09
2	Ref PWD SCHEDULE 2017 Page No-34, Item No-						
	22 (I) Cement concrete						
	with graded stone ballast (40 mm size excluding						
	shuttering) In ground floor						
	(A) [Pakur Variety]						
	(a) 1:3:6 proportion	0.585	Cu.M	₹	5,190.00	₹	3,036.15
	Ramp	0.360	Cu.M	₹	5,190.00	₹	1,868.40
3	Item no-8/page no-15						
	Brick work with 1st class bricks in cement mortar						
	(1:6) Up to GL	1.463	Cu.M	₹	5,306.00	₹	7,760.03
	GL TO PL	1.950	Cu.M	₹	5,306.00	₹	10,346.70
4	Item No-4/Page No-2						
	Filling in foundation or plinth by silver sand in						
	layers not exceeding 150 mm as directed and						
	consolidating the same by thorough saturation						
	with water, ramming complete including the cost						
	of supply of sand. (payment to be made on						
	measurement of finished quantity)	5.228	Cu.M	₹	936.21	₹	4,894.92



(Formerly WEST BENGAL UNIVERSITY OF TECHNOLOGY)

<u>Main Campus: NH 12, Haringhata, Post Office - Simhat, Police Station – Haringhata, Pin - 741249</u>
<u>City Campus: BF-142, Sector -I, Salt Lake, Kolkata -700 064</u>

5	there we 1/Pers we 47			 			
	Item no-1/Page no-47						
	25mm. thick damp proof course with cement						
	concrete with stone chips (1:1.5:3) [with graded						
	stone aggregate 10 mm nominal size] and						
	admixture of water proofing compound as per						
	manufacturer's specification followed by two						
	coat ofpolymer based paint, (1st coat after 4 to 5						
	days of concretelaying and 2 nd coat just before						
	brick masonry work) as directed (cost of water						
	proofing compound & polymer based paint to be						
	paid separately).(Chequering not required over						
	concrete or painted surface). [Note: -						
	aterproofing as per item 9, polymer based paint						
	as per item 8 (a) of subhead C of Section (C).	6.500	Sq.m	₹	186.00	₹	1,209.00
6							
	Item no-16/page no-16						
	125 mm. thick brick work with 1st class bricks in						
	cement mortar (1:4) in ground floor.	13.000	Sq.m	₹	724.00	₹	9,412.00
7	Item No-1/Page No-189						
	Plaster (to wall, floor, ceiling etc.) with sand and						
	cement mortar including rounding off or						
	chamfering corners as directed and raking out						
	joints including throating, nosing and drip course,						
	scaffolding/staging where necessary (Ground						
	floor).[Excluding cost of chipping over concrete						
	surface] (ii) With 1:4 cement mortar						
	(a) 20 mm thick plaster	32.775	Sq.m	₹	186.00	₹	6,096.15
8							
	Item No-15/Page No-192						
	Neat cement punning about 1.5mm thick in wall,						
	dado, window sill, floor etc.						
	NOTE:Cement 0.152 cu.m per100 sq.m.	37.050	Sq.m	₹	34.00	₹	1,259.70
9	Item No-1/Page No-14						·
	Single Brick Flat Soling of picked jhama bricks						
	including ramming and dressing bed to proper						
	level and filling joints with local sand.(Flooring)						
	To the area many joined than to an earlier (1.00 m/g)	34.856	Sq.m	₹	358.00	₹	12,478.54
10	Ref PWD SCHEDULE 2017 Page No-34, Item No-						
	22 (I) Cement concrete						
	with graded stone ballast (40 mm size excluding						
	shuttering) In ground floor						
	(A) [Pakur Variety]						
	(a) 1:3:6 proportion						
		2.614	Cum	₹	5,190.00	₹	13,567.80
	Plinth protection						
		1.686	Cum	₹	5,190.00	₹	8,750.34



(Formerly WEST BENGAL UNIVERSITY OF TECHNOLOGY)

Main Campus: NH 12, Haringhata, Post Office - Simhat, Police Station - Haringhata, Pin - 741249

<u>City Campus: BF-142, Sector -I, Salt Lake, Kolkata -700 064</u>

11	Item No-1/Page No-189 Supplying, fitting and fixing 18 mm. to 22 mm. thick kota stone slab in wall, dado in 15 mm thick [avg] cement mortar (1:3) including making suitable arrangement to hold the stone properly by brass / copper hooks including pointing in cement mortar (1:2) (1 cement : 2 marble dust) with admixture of pigments matching the stone shade, including grinding and polishing all complete as per direction of Engineer-in-charge including cost of materials, labour, scaffolding, staging, curing complete. [Using cement slurry for bedding @4.4 kg/Sq.m and for jointing @1.8 kg/Sq.m]	36.094	Sq. M	₹	1,154.00	₹	41,652.19
12	Item No-2(A)/Page No-101 M.S. structural works with hollow sections (square or rectangular shape) conforming to IS: 806-1968 & IS:1161-1998) connected to one another with bracket, gusset, cleat as per design, drawing & direction of Engineer-in-Charge complete including cutting to requisite shape & size, fabrication including metal arc welding conforming to IS: 816-1969 & IS: 9595 using electrodes of approved make and brand conforming to IS:814- 2004, haulage, hoisting and erection all complete. The rate includes the cost of all M.S. Hollow ection, all consumables such as electrodes, gas and hire charges of all tools and plants and labour reqired for execution and all incidental chages (such as electricity, labour nsurance) etc. complete. Payment to be made on the basis of calculated weight of structural memebrs of MS Holow Section as specified in relevent IS code in finished work. Payment for gusset, bracket, cleat may be made by adding the actual weight of such items with weight of finished structural members. The rates are considered for a hight of erection 8 m. / 2nd floor level from the ground. Add 1.5 % extra over the rate for each additional floor or 4m. beyond the initial 8 m. or part thereof. i) For roof truss works a) Span up to 12 Mtr						
13	Item No-14/Page No-82 Supplying, fitting & fixing Zn-Al alloy (55% Al & 45% Zn) coating of 150 grams per sq. metre ollowed by colour coated on both side) steel sheet work having minimum yield strength of 550 Mpa of trapizoidal profile of approved make (excluding the supporting frame work) fitted and fixed with 55 mm & 25 mm self tapping screw, EPDM Washer 16 mm dia & 3 mm th. washer etc. complete with 150 mm end lap and one	626.325	Kg Sq.m	₹	58.83 787.00	₹	36,847.95 47,832.10



 $(Formerly\ WEST\ BENGAL\ UNIVERSITY\ OF\ TECHNOLOGY)$

<u>Main Campus: NH 12, Haringhata, Post Office - Simhat, Police Station – Haringhata, Pin - 741249</u>
<u>City Campus: BF-142, Sector -I, Salt Lake, Kolkata -700 064</u>

	corrugation minimum side lap. (Payment to be made on area of finished work).						
		40.000		_		_	44.00=.05
4.4	Two side's	18.980	Sq.m	₹	787.00	₹	14,937.26
14	Item No-1/Page No-200						
	(a) Priming one coat on steel or other metal surface with synthetic oil bound primer of						
	approved quality including smoothening surfaces						
	by sand papering etc	32.000	Sq.m	₹	29.00	₹	928.00
15	Item No-2/Page No-200			-		-	
	(A) Painting with best quality synthetic enamel						
	paint of approved make and brand including						
	smoothening surface by sand papering etc.						
	including using of approved putty etc. on the						
	surface, if necessary :						
	(b) On steel or other metal surface						
	(iv) Two coats (with any shade except white)	32.000	Sq.m	₹	79.00	₹	2,528.00
		Total			₹	2,25,684.30	
		Add 5% Electrical cost			₹	11,284.22	
		Sub total			₹	2,36,968.52	
		Add GST 12%			₹	28,436.22	
		Sub total			₹	2,65,404.74	
		Add labour cess 1%			₹	2,654.05	
		Grand Total				2,68,058.79	
		SAY					2,68,059.00

Sd/-Registrar MAKAUT, WB