

WEST BENGAL UNIVERSITY OF TECHNOLOGY
BF – 142, SEC-I SALT LAKE CITY
KOLKATA- 700064

TENDER NOTICE

No : Engg/Tender/01/14

Date :04/03/2014

Sealed Tender are invited from bonafide, resourceful experienced PWD/UNIVERSITY/ GOVT etc contractors with valid IT, VAT, P.TAX certificate with credentials of 50% of the estimated cost, for the below mentioned work.

Name of the work : Construction of a Aluminium Framed Glazed Cubical and other Allied work in Room no – L-3, Gr.Fl./ Production Engg lab of

West

Bengal University of Technology campus, Saltlake.

Estimated Cost : Rs 1,66,158/-

Earnest Money : Rs 3,000/-

Tender Fee : Rs 300/- (Non – Refundable)

Time of Completion : 21 days.

Last date of submission tender : 21/03/2014 up to 2.00 p.m.

The Contractors should filled up the tender along with signature & seal. An amount of Rs 300/- (Rupees Three Hundred Only) through Pay Order/ Bank Draft in favour of “West Bengal University of Technology “ Payable at kolkata(Non Refundable) as cost of tender.The tender paper should be submitted in a sealed cover addressed to the Registrar of the university super scribing the name of the work along with Rs 3000/- (Three Thousand Only) in Pay Order/ Bank Draft as earnest money deposit in favour of “West Bengal University of Technology” Payable at kolkata.

The contractor should quote rate Percentage (Above/ At PAR/ Below) of the amount put into the Tender.

The specification of PWD Schedule will be followed.

The rate and amount should be quoted in figure and words.

The university has right to accept or reject any Tender without assigning any reasons.

Contd.....

(2)

The quantity mentioned in the tender may increase or decrease as per site condition.
The item which are needed but not in the scope of work will be operated as per
PWD
Schedule of rates. If not in the PWD schedule then the market rate will be applicable.
The schedule of work is attached.

(Registrar)

Contd---

-

(3)

Schedule of work for Cubical in Room No – L 3, Gr. Floor/ Production Engg. Lab.

Sl no	Particulars	Qty	Rate	Amount
1.	Supply, fitting, fixing, and erection of a cubicle made of aluminium(ISI make) natural anodized with 65mmx 37mm hollow section (1.2 mm thk) for post and other member of partition wall with 09mm thk particle board at bottom 1200 mm wide and Best Indian sheet glass panes of 5mm thk of 1000 mm wide and remaining portion with laminated particle board about 01 M including labour and materials in complete.	25 Sq.m.	@ Rs 2650/ Sq,m.	Rs 66250
2.	Aluminium sliding door of section (ISI make) 75 mm x 45 mm and bottom with 95 mm x 45 mm of natural anodized with 09mm particle board 1200 mm wide at lower and remaining with 5mm clear glass including locking arrangement , handle, with labours, materials in complete.	06 Sq.m	@ Rs 4165/ Sq,m	Rs 24990
3.	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacture's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer.			
a)	Normal Acrylic Emulsion	175 sq.m	@ 72.92/ Sq,m	Rs12761

Contd -----

(4)

4. Supplying and laying of approved make and brand of scratch proof, flexible, & homogeneous P.V.C Vinyl flooring conforming to IS : 3462 - 1982 in required finished, fixed with synthetic acrylic adhesive after preparing the floor, leveling and smoothening when necessary with suitable putty, as per the design and instruction of the EIC.

a) 02 mm thk	98 Sq.m	@ 430.18/ Sq.m Rs 42157
--------------	---------	----------------------------

5. Misc Work

(The Payment to be made as per item and

Specification of PWD Schedule of rates 2010)	L.S	Rs 20000
--	-----	----------

Total : Rs 1,66,158/-

(One Lacks Sixty Six Thousand One Hundred Fifty Eight Only)

I/ We offer -----% (Above/AT PAR/ Below) of the tender amount for the above work as per attached schedule and abide by all the terms and conditions.
(Strike out which are not applicable)

(Seal of the contractor with signature)