

**WEST BENGAL UNIVERSITY OF TECHNOLOGY
BF-142 , SEC-I , SALT LAKE CITY ,
KOLKATA- 700052**

TENDER NOTICE

NO : ENGG/24

DATE : 24/02/2012

Sealed tender are invited from bonafide , resourceful , and experienced PWD /University /CPWD etc contractors with valid I.T., S.T certificate for the below mention work.

Name of the Work: The supply and erection of C.I of Spiral Stair case at Saltlake Campus of University of Technology.

Estimated Cost : : Rs 94,330 /-

Earnest Money Deposit : : Rs 1,887 /-

Time of Completion : One month

The tender paper may be had from the office of the Engineer (Civil)of University on and from 12/03/2012 to 16./03/2012 from 11.00 am to 2.00 P.M. with a payment of Rs 200/- (Rupees Two hundred only) by Payorder/DD in favour of “ West Bengal University of Technology”payable at kolkata. The last date of submission of tender paper 21/03/2012 upto 3.00pm .The tender will open on the same day at 3.30pm in presence of tenderers. The tenders should be submitted to the Registrar , W.B.U.T.

—

Registrar

WEST BENGAL UNIVERSITY OF TECHNOLOGY
BF-142 , SEC-I , SALT LAKE CITY ,
KOLKATA- 700052

No : ENGG/24

Date : 24/2/2012

Name of the work : Supply & Errection of Spiral Stair Case at W.B.U.T campus
BF – 142, Sec –I , Saltlake City Kolkata – 700064.

Estimated Cost : Rs 94,330 /-

Earnest Money Deposite : Rs 1,887 /-

Time of Completion : One month

<u>Description of work</u>	<u>Qty</u>	<u>Rate</u>	<u>Amount</u>
1. Supply ,fitting & fixing cast iron heavy type Spiral Stair Case of approved designed with 50 mm dia stem & C.I steps 150mm as per designed 900mm high C I railing including necessary MS tie of suitable section embedded to with cement concrete (1:2:4) including cost of intermediate CI platform secured with necessary tie to stem & wall with cement concrete (1:2:4) including fixing the stem in ground with cement concrete (1:3:6) complete in all respect with all labours & materials . (payment to be made on vertical height in between 1 st step & top platform)			
a. With 1200mm dia wall	15m	4766.44/m	71496.60
2. Dismantling all types of masonry excepting cement concrete plain or reinforced ,stacking serviceable materials at site and removing rubbish as directed with in a lead of 75m.			
a)In ground floor including roof	3cum	276.64/cum	829.94
b) Extra rate for each addl floor over the rate of ground floor	3cum	306.64/cum	919.92
	3cum	336.64/cum	1009.92
3. 125mm thick brick work with 1 st class brick In cement mortar(1:3) in ground floor .	2sqm	558.94/sqm	1117.88

<u>Description of work</u>	<u>Qty</u>	<u>Rate</u>	<u>Amount</u>
a) Add extra for each additional floor over the rate for ground floor			
i) 1 st floor	2sqm	566.08	1132.16
ii) 2 nd floor	2sqm	573.22	1146.44
4. Plaster (to wall , floor , ceiling, etc) with sand and cement mortar .			
a) with 1:4 cement mortar- 20mm thk	12sqm	146.19/sqm	1758.72
5. Ordinary cement concrete (1:2:4) with graded stone chips (20mm nominal size)	0.8cum	5001.28/cum	4000.8
6. MS or WI ornamental grill gate of approved Design			
a) Grill weighing above 16kg /sqm and above	1.21qtl	6382.19/qtl	7722.45
7. Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality	12sqm	28.38/sqm	340.56
8. Painting with best quality synthetic enamel paint of approved make and brand			
a) On steel or metal surface			
i) Two coats (with any shade except white)	11.34sqm	54.14/sqm	613.94
9. Dry distempering to interior walls or ceiling			
a) Two coats	12sqm	32.32/sqm	387.84
Contingency 2%			Rs- 92477.17 1849.54

	Total -		Rs-94326.71
	Say -		Rs-94,330 /-

Registrar

WEST BENGAL UNIVERSITY OF TECHNOLOGY

Name of the work : Supply & Errection of Spiral Stair Case at W.B.U.T campus
BF – 142, Sec –I , Saltlake City Kolkata – 700064.

Terms & Conditions

1. The earnest money deposit is Rs1887/- (One Thousand Eight hundred Eighty seven)& the earnest money should be deposited in favour of 'West Bengal University of Technology'.
2. The earnest money will be refunded to the unsuccessful tenderers.
3. The earnest money will be converted to security deposit for the successful tenderer.
4. The security deposit @8% will be deducted from each bill.
5. The tenderer should quote the percentage above / below / at par of the estimated cost put in the tender .
6. The work will be done as per specification of P.W.D.
7. The time of completion is 30 days from the date of issue of work order .
8. The rate should quoted in figure and as well as word .
9. Term & Condition in W.B.Form 29 11 (ii) would remain applicable .
10. Tenderers should superscribe the name of the work on top of the envelope.
11. The authority has right to accept or reject any tender without assigning any reason.