

MAULANA ABUL KALAM AZAD UNIVERSITY OF TECHNOLOGY, WEST BENGAL

No : ENGG(Civil)/Tender-02/2015

Date : 10.09.2015

Sealed tenders are invited for construction of Cubicles by providing aluminum partially glazed partition wall in Room No - L-3 at the campus of MAKAUT, BF-142, Sec-I, Saltlake Kolkata : 700064 from experienced and resourceful agencies who have qualified the following conditions .

Name of the work : construction of Cubicles by providing aluminum partially glazed partition wall including false ceiling in the Room No - L-3 at the campus of MAKAUT, BF-142, Sec-I, Saltlake Kolkata : 700064.

Estimated Cost : Rs 1,21,973 /-

Issue of Tender documents: 14/09/2015 to 21.09.2015 upto 2.30 PM

Last date of submission of complete tender: 23/09/2015 upto 2.30 PM

Opening of tender: - 23/09/2015 at 3.30 PM

Earnest money deposit: Rs 2500/-

Time of completion : 15 days from the date of handing over the site.

1. Qualifications required for participating in the tender.

- i) The bidder must have IT, ST, VAT, PT, etc. clearance certificates.
- ii) The bidder must have credential of completion of similar type of Job/ civil & Interior work of minimum amount of Rs 5.00 Lac executed within 05 years from the date of publication of the NIT.
- iii) The bidder must have annual turnover average of Rs 10 lac in last 03 financial years.
- iv) The bidder should submit the audited balance sheet for the last three financial years.

2. The bidder shall submit the EMD in the form of DD/Pay Order of any nationalized bank payable in favour of 'Maulana Abul Kalam Azad University of Technology, West Bengal'. The EMD of successful bidder shall be converted as initial Security deposit. The EMD shall remain valid for three months from the date of opening of tender.

3. Security deposit

The Security deposit along with the initial security deposit shall be 10% of the ordered amount which shall be realized from first and final bill. The security deposit shall be released 06 months after the completion

of the job being certified by controlling officer/E-I-C and within such period the contractor shall be liable for maintaining/repairing of the defects .

4. Engineer-in -Charge/Controlling Officer

The Engineer(Civil),MAKAUT.

5. Paying Authority

The Finance Officer, MAKAUT.

6. Penalty :

The university shall impose penalty in the event of failure of the contractor to complete the work in the stipulated time or abandonment of the work at his own fault.. The penalty shall be deducted @ 10% Of the ordered amount with forfeiture of the EMD.

7. Mode of Work

The work must be executed strictly as per the enclosed schedule of works and as per Specification and rates of PWD S.O.R. (Bldg) w.e.f July' 2014.

8. Variation of work

The rates shall be inclusive of all taxes and duties and Service tax. However the rate shall remain firm until total executed amount exceeds 25% of the ordered amount. The amount of work may vary upto (+ or -) 25%.

9. The bidders must quote rate in the price bid as enclosed in annexure-I as % above or below.

10. No quotation shall be entertained if EMD is not submitted. The university authority reserves the right to reject offer of any bidder or canceled the tender without assigning any reasons.

11. The tender must be submitted to the Engineer(Civil), MAKAUT, WB.

sd/-
Engineer(Civil)
MAKAUT,WB

PRICE BID (ANNEXURE-I)

construction of Cubicles by providing aluminum partially glazed partition wall including false ceiling in the Room No - L-3 at the campus of MAKAUT, BF-142, Sec-I, Saltlake Kolkata : 700064.

SI No	DESCRIPTION OF ITEM	QTY	UNIT	RATE(RS)	AMOUNT(RS)
1	Supply, fitting, fixing, and erection of a cubicle made of aluminum natural anodized with 65mm x 37mm hollow section(1.2mm thick) for post and other member of partition wall with 9mm thick particle board at bottom 1200mm wide and best Indian sheet glass panes 5mm thick remaining portion excluding 450mm wide top with particle board Including labor and material complete.	21	M ²	3000	65,100
2	Aluminum sliding door of section 45mmX 50mm and bottom with 95mm X 45mm of natural anodized with 9mm particle board 1200mm wide at lower and remaining with 5mm glass including labor materials complete.	3	M ²	4500	13,500
3	Supplying by laying approved make and brand of scratch proof flexible and homogeneous PVC Vinyl flooring conforming to IS 3462 1982 in required finish fixed with synthetic acrylic adhesive after preparing the floor, leveling and smoothing when necessary with suitable putty as per the design and instruction of the EIC. 2mm thick	45	M ²	583	26,235

4	<p>Providing and fixing of false ceiling with powder coated exposed GI grade supervision system(E Grid U 1520 or equivalent load carrying capacity with mid span deflection not excluding 1/360 span with hangers spacing of 1200 mm c/c) considering of main runner 3600mm long, cross tee 1200mm /600mm long and wall angle. The wall shall be fixed on PVC Dash fastener on the perimeter of the wall by steel screw with distance 300mm c/c. The main runner to be placed at the rate of 1200mm. the cross tee 1200mm will be inserted in the pre cast slots of main runner at regular interval of 600mm to form a modular grid of 1200mmX 600mm. Additional cross tee of 600mm shall be placed perpendicular to the cross tee 1200mm long to finally form a grid of 600X600mm. Grid of module size 600X600mm shall be supported by 6mm dia. G.I wire from purline/soffit. 15mm thick OW acoustic board(mineral fiber acoustic ceiling tiles) of approved pattern and size 606X606mm with NRC value > 0.65</p> <p>a) Acoustic false ceiling(With 15mm thick OW acoustic board and ES grid U 1520)</p>	12.5	M ²	1371	17,137.50
	TOTAL AMOUNT				1,21,972.50

I/WE declare our offer ----- % above/below the total amount of Rs 1,21,972.50